

Safety Golden Rules



SCAN &
WATCH
THE
VIDEOS



1. Start Safe

Always check the job is safe. SWMS must be in place for ALL High Risk Construction Works. JSEA for all other works. START Card to be completed and signed onto by all personnel prior to commencing all works.




6. Driving Vehicles

Always plan your trip to allow time to arrive safely and follow all road rules. Drivers must be fit to operate with a BAC of 0.00.




2. Cranes & Lifting

Always keep clear of exclusion zones, suspended loads and lifting operations.



7. Energised Equipment

Always isolate all energy sources and verify the isolation is effective before working on equipment. **Permit to Work Required**



3. Working at Height

Always ensure there is a fall protection, prevention or arrest in place before working at height, including when working over water. **Permit to Work Required.**



8. Electrical Equipment

Always check electrical equipment is free of faults, tagged according to date schedule, leads are off the ground on insulated supports and clear of water and traffic paths. **Permit to Work Required**



4. Working Near Mobile Plant

Always keep clear of moving plant and don't enter the operating zone without a positive signal from the operator. allowable limits.



9. Trenching & Excavation

Always check trenches over 1.5 m are battered, benched or shielded before entering and barricade and sign open trenches. **Permit to Work Required**



5. Operating Mobile Plant

Always advise others working nearby before you start operating mobile plant and stop your machine and signal others when it is safe for them to pass.



10. Confined Space

Always ensure only trained personnel enter a confined space after they have checked the atmosphere is safe and the required rescue equipment and a stand-by sentry is in place. **Permit to Work Required**

HOME
WITHOUT
HARM

**MCCONNELL
DOWELL**
CREATIVE CONSTRUCTION™